### ADDENDUM FOUR

Memorial Park Improvements 604 Hazel Street Auburn, IN 46706

MARTINRILEY architects/engineers 221 West Baker Street Fort Wayne, Indiana 46802 260-422-7994

Commission No.: F23059

Addendum Date: 20 August 2024

**Conditions:** The following clarifications, amendments, additions, deletions, revisions and modifications are a part of the contract documents and change the original documents only in the manner and to the extent stated.

Copies of the Addendum shall be bound with all contract sets of drawings and specifications.

#### **CLARIFICATIONS:**

See answers to contractor questions below.

#### **Contractor Question #15**

Are the cameras wireless? If not, how and where are the fed from? Do the cameras need 120v power. If so, there are no circuit numbers on prints.

The cameras are wired Cat6A and are fed by head-end unit from the data rack in the mechanical room.

#### **Contractor Question #16**

Do the cameras need 120v power? If so, there are no circuit numbers on prints. Are all cameras mounted on 35 foot poles? (other than the (2) on the restroom building and (1) on the pavilion). For instance, the (2) cameras by the pickleball courts and the (1) by the baseball diamond do not have a pole shown.

PoE to all cameras with extenders at the pavilion for the (3) Southeast cameras because of distance. Pickleball and baseball cameras to be mounted on 35ft poles.

#### Contractor Question #17

I do not see the louver in a schedule, I have not seen it addressed in the addenda. Are we to supply and Install? If so what are the specs?

The exhaust louver shall be a 6" deep extruded aluminum wind-driven rain louver with horizontal blades similar to Greenheck EHH-601. The louver shall have exterior dimensions of 16"x16" and finish color to be selected by the Architect. The louver shall be installed such that it is aligned within the CMU block grid on the exterior wall.

### **Contractor Question #18**

There are no specifications for the color coat system on the pickleball courts, only the color scheme. Can you clarify what you want?

See revision to sheet C800 below.

#### CHANGES TO THE SPECIFICATIONS:

• No specification changes at this time

#### **CHANGES TO DRAWINGS:**

Sheet E100 - DELETE sheet in its entirety and REPLACE with the attached revised E100:

- ELECTRICAL SITE PLAN:
  - ADD work description note #1 to the three additional pole locations by the baseball field and pickleball courts

Sheet C800 - ADD following note to detail 6/C800:

- NOTE: Pickleball Court System
  - (2) 6-mil vapor barrier layers prior to cable placement.

Medium Broom Finish and acid etched

Pressure wash surface and allow to dry before applying Color System.

**Ensure Level** 

Basis of Design:

Laykold Colorcoat System - Installed according to the manufacturer's instructions

Lavkold Bond-Kote

Laykold Acrylic Resurfacer


Laykold Topcoat

Laykold Line Primer and Textured White Line Paint

#### **ATTACHMENTS:**


F23059 Memorial Park Auburn - E100.pdf

#### END OF ADDENDUM NUMBER FOUR



# Work Description Notes

- 1 REFER TO 3/E501 POLE MOUNT DETAIL



- 1. ALL WORK TO BE PERFORMED IN ACCORDANCE WITH STATE AND LOCAL CODES & AMENDMENTS.
- GIVEN FOR FORESEEABLE WORK COORDINATION.
- EXISTING, FROM DUST DEBRIS AND DAMAGE. FINAL CLEAN-UP SHALL BE PERFORMED TO PROVIDE A CLEAN, DUST FREE ENVIRONMENT TO THE OWNER.
- CIRCUIT: 65 FEET #12, 110 FEET #10, 165 FEET #8, 270 FEET - #6 8. PROVIDE ADDITIONAL DERATING PER NEC SECTION 310 FOR ALL HOME RUNS WITH MORE THAN THREE CURRENT
- 9. SHARING OF NEUTRALS SHALL NOT BE PERMITTED.

## Electrical Legend

SEE TITLE SHEET FOR ADDITIONAL SYMBOLS AND ABBREVIATIONS. SYMBOLS IN THIS LIST ARE NOT DRAWN TO SCALE SYMBOLS IN THIS LIST, MAY NOT APPLY TO THIS PROJECT HEIGHTS LISTED HERE APPLY UNLESS NOTED OTHERWISE HEIGHTS ARE TO THE BOTTOM OF THE DEVICE

- LIGHT FIXTURE; EMERGENCY/NIGHT

- SINGLE POLE SWITCH; +44" AFF
- THREE-WAY SWITCH; +44"AFF
- OCCUPANCY SENSOR WALL MOUNTED

- DUPLEX RECEPTACLE; +16" AFF

- M MOTOR
- SECURITY CAMERA +84" AFF
- PUSHBUTTON
- FIRE ALARM STROBE +80" AFF
- FX MANUAL PULL STATION WITH HORN/LIGHT
- HEAT DETECTOR

- ML MAGNETIC LOCK
- TAMPER SWITCH
- SPEAKER

### General Electrical Notes

- 2. SEE SPECIFICATION BOOK FOR ADDITIONAL
- REQUIREMENTS. PROVIDE EVERYTHING NECESSARY TO MAKE REQUIRED SYSTEMS AND FEATURES COMPLETE AND FUNCTIONAL; INCLUDING BUT NOT LIMITED TO: FITTINGS, ADAPTERS, WIRE, BOXES, RACEWAY, HARDWARE, TEMPORARY
- CONNECTIONS AND SUPPORTS. 4. DRAWING ORGANIZATION IS NOT TRADE SPECIFIC AND IS NOT INTENDED FOR DIVISION OF WORK AMONG SUBCONTRACTORS. THE GENERAL CONTRACTOR IS RESPONSIBLE TO PROPERLY DISSEMINATE WORK ON ALL SHEETS AND COORDINATE WITH EVERY SUBCONTRACTOR
- IN ORDER TO PROVIDE A COMPLETE PROJECT. 5. ELECTRICAL DRAWINGS ARE SCHEMATIC IN NATURE. ALL DEVICES AND EQUIPMENT ARE SHOWN IN APPROXIMATE LOCATIONS. CONTRACTORS TO COORDINATE THEIR WORK WITH ALL OTHER TRADES ON SITE. EXTRAS WILL NOT BE
- 6. PROTECT ALL EQUIPMENT AND FINISHES, NEW AND
- EXCEPT WHERE NOTED OTHERWISE, SIZE BRANCH CIRCUIT CONDUCTORS WITHIN THE FOLLOWING MAXIMUM LENGTH LIMITS: (MEASURE TO THE CENTER OF THE LOAD FOR LIGHTING AND MOST REMOTE OUTLET FOR RECEPTACLE CIRCUITS). MINIMUM CONDUCTOR SIZE FOR 120V 20A
- CARRYING CONDUCTORS IN A SINGLE RACEWAY.
- 10. PROVIDE BACKBOX AND 3/4" CONDUIT TO ATTIC WITH PULL WIRE FOR ALL TELEPHONE/DATA/AUDIO OUTLETS.



COMPONENTS SHOWN IN GRAY ARE EXISTING OR SPECIFIED IN OTHER VIEWS.

- HOME RUN TO PANEL & CIRCUIT NO.
- XX MARK FOR SCHEDULED ITEM
- LIGHT FIXTURE; CEILING MOUNTED
- O DOWNLIGHT FIXTURE; CEILING MTD./EXTERIOR
- C LIGHT FIXTURE; WALL MOUNTED.
- ← EMERGENCY LIGHT WALL PACK.
- MOTION DETECTOR SWITCH; +44" AFF
- ♦ EXIT LIGHT; CEILING MOUNTED; DIRECTIONAL
- PANEL BOARD (SURFACE MOUNT); +72" AFF
- SAFETY DISCONNECT SWITCH; NON FUSED, +66" AFF TO TOP XX XX DENOTES AMPERE RATING
- CBH SAFETY DISCONNECT SWITCH; CIRCUIT BREAKER, +66" AFF TO TOP XX DENOTES AMPERE RATING
- SAFETY DISCONNECT SWITCH; FUSED, +66" AFF TO TOP XX DENOTES AMPERE RATING
- TRANSFORMER
  XX XX DENOTES KVA RATING
- DOUBLE DUPLEX RECEPTACLE; +16" □ DEDICATED RECEPTACLE; +16" AFF
- JUNCTION BOX ▼ TELEPHONE/DATA OUTLET +16"
- PHOTOCELL
- KP KEY PAD FIRE ALARM HORN/STROBE +80" AFF
- F MANUAL PULL STATION
- S SMOKE DETECTOR SMOKE & CARBON MONOXIDE DETECTOR
- DUCT SMOKE DETECTOR MAGNETIC DOOR HOLDER
- FLOW SWITCH
- FAAP FIRE ALARM ANNUNCIATION PANEL FACP FIRE ALARM CONTROL PANEL



Improvements

ark

 $\Box$ 

Memorial



221 West Baker Street pho 260.422.7994 fax 260.426.2067 Fort Wayne, Indiana 46802 No. 10403287

1 BID SET



2 Addendum 2

3 Addendum 4

DATE: 2024-06-28

2024-07-16

2024-08-07

2024-08-20

ELECTRICAL SITE PLAN