



Addendum No. 2

Project: Expand Hangar 2003 Apron
FWACAA Project No. AF25-08

CHA Project No.: 098067.000

Date: July 15, 2025

The following addendum items modify, change, delete from or add to, the requirements of the contract documents for this project. The articles contained in the addendum take precedence over the requirements of the previously published contract documents. Where any article of the contract specifications or any detail of the contract drawings is modified or any paragraph, subparagraph or clause thereof is modified or deleted by the articles contained in this addendum, the unaltered provisions of that article, paragraph, subparagraph or clause shall remain in effect.

ITEM NO. 1 – SPECIFICATIONS

General Note – Unless noted to be reissued with this addendum, the following specifications revisions will be incorporated as part of the “Issued for Construction” specification booklet.

Item P-154 – Subbase Course

Revision: Section 154-2.4 Geogrid is revised to read as follow:

154-2.4 Geogrid. Geogrid material shall be multi-axial provided in accordance with INDOT 918 **Type IB**.

ITEM NO. 2 – QUESTIONS

Question #1: Can you clarify the intent of Pay Item No. 13, the allowance for additional mobilization of Lime-Treated Subgrade?

Response #1: Because corresponding Pay Item No.'s 40 and 41 for Lime-Treated Subgrade are shown to be Undistributed, or to be used as needed, the allowance under Pay Item No. 13 has been included to capture the corresponding mobilization and demobilization of the specialty contractor/equipment such that this cost would not be spread across other distributed pay items.

In the event field conditions warrant the need to use lime treatment for the subgrade soils, the corresponding costs for mobilizing (and demobilizing) the specialty subcontractor and/or equipment shall be captured under this allowance, to be measured and paid for as time and materials per Special Provision SGP-17, and as described in Technical Provision Item C-105.

Sincerely,


Nathan Lienhart, P.E.
Senior Project Manager



07/15/2025