

ADDENDUM NO. 3

To the Contract Document and Project Specifications for the

BLACKHAWK MIDDLE SCHOOL SITE IMPROVEMENTS

Fort Wayne Community Schools (FWCS)

Fort Wayne, Indiana

October 21, 2025

To: All holders of the contract documents for the above project.

The items in this addendum are to become a part of the original documents as if included therein. The remainder of the original contract document is to remain in its entirety. This Addendum modifies the Contract Documents and Specifications as follows:

Part 1 – General Clarifications

Part 2 – Specifications

Part 3 – Construction Drawings/Details

Part 4 – Questions

PART 1 – GENERAL CLARIFICATIONS

1. None included

PART 2 – SPECIFICATIONS (Replace - See Attached)

1. None included

PART 3 – CONSTRUCTION DRAWING / DETAILS (Replace - See Attached)

1. Plan Sheet E000 – Electrical Coversheet

REMOVED: Language requiring pressurized grout for directional drilling.

OTHERWISE NOTED	
UNDERGROUND SITE CONDUITS:	
	WITHIN 5' FROM THE PERIMETER OF A BUILDING FOUNDATION
	5' OR GREATER FROM THE PERIMETER OF A BUILDING FOUNDATION
	UNDER ROADS, DRIVES, AND VEHICLE TRAVELED WAYS

2. Plan Sheet E600 – Electrical Schedules

REVISED: Language pertaining to item S3A to lower the lumens output for the light located near the pickup lane entrance.

S3A	AREA LIGHT SQUARE, DUAL HEADS, 20'-0" SQUARE (STRAIGHT STEEL POLE, TYPE V WIDE DISTRIBUTION, BRONZE FINISH)	A	PL 20'-0"	1'-10"	1'-3"	5 1/2"	0"	220	FIX	LED	2	12,000 EACH HEAD	480	LITHONIA RSX1-LED-P3-40K-R5-HVOLT-SPA-DBLXD CURRENT LIGHTING (2) ASL1-160L-100-4K7-5QW-480-A-DBT / SSSH25-40A-1-B3-DBT LUMARK (2) PRV-PA2A-740-8-5WQ-SA-BZ / VS-SSSA-15-4040-11-AB-FP-DB-D2 LITHONIA (2) RSX1-LED-P3-40K-R5-HVOLT-SPA-DBLXD
S3B	AREA LIGHT SQUARE, DUAL HEADS, 20'-0" SQUARE (STRAIGHT STEEL POLE, TYPE V WIDE DISTRIBUTION, BRONZE FINISH)	A	PL 20'-0"	1'-10"	1'-3"	5 1/2"	0"	220	FIX	LED	2	15,000 EACH HEAD	480	LITHONIA RSX1-LED-P3-40K-R5-HVOLT-SPA-DBLXD CURRENT LIGHTING (2) ASL1-160L-100-4K7-5QW-480-A-DBT / SSSH25-40A-1-B3-DBT LUMARK (2) PRV-PA2A-740-8-5WQ-SA-BZ / VS-SSSA-15-4040-11-AB-FP-DB-D2 LITHONIA (2) RSX1-LED-P3-40K-R5-HVOLT-SPA-DBLXD
2	12,000 EACH HEAD													LITHONIA RSX1-LED-P3-40K-R5-HVOLT-SPA-DBLXD CURRENT LIGHTING (2) ASL1-160L-100-4K7-5QW-480-A-DBT / SSSH25-40A-1-B3-DBT LUMARK (2) PRV-PA2A-740-8-5WQ-SA-BZ / VS-SSSA-15-4040-11-AB-FP-DB-D2 LITHONIA (2) RSX1-LED-P3-40K-R5-HVOLT-SPA-DBLXD
2	15,000 EACH													CURRENT LIGHTING (2) ASL1-160L-115-4K7-5QW-480-A-DBT / SSSH25-40A-1-B3-DBT

PART 4 – QUESTIONS

- Looking at the site removals plan and the new conduit required, it appears most of the conduit required will need to be bored. In the conduit installation schedule on sheet E000, in the bottom line for conduit installed “Under roads, drives, and vehicle traveled ways. When HDPE directional boring is allowed: provide pressurized grout.” Given that we do believe it will be HDPE bored, is the pressurized an actual requirement for this project?

A. Please see the revised plans included within this addendum removing the requirement for pressurized grout.